

ADDENDUM

ADDENDUM NO.: 1(one)

DATE: 2/15/2021

PROJECT IDENTIFICATION

PROJECT NAME: Kirkwood Schools Roof Replacement Project-2021

PROJECT NUMBER: Early Childhood Center

SITE ADDRESS: 200 Thomas Avenue (Facilities Office)

Street Address

Kirkwood,

MO

63122

City

State

ZIP Code

(314)213-6100 x8501

(314)965-9598

Site Telephone

Site Fax

ADDENDUM

The following is a summary of changes to the plans and Specifications that shall be considered as a part of your Bid. Receipt of this Addendum shall be acknowledged on the Bid Proposal Form.

This Addendum consists of 1 pages.

SUMMARY OF ADDENDUM:

1 New-The EPDM needs to be applied with CavGrip or another odorless adhesive. Peel & Stick membranes are acceptable.

2 Change: The Solar Contractor needs to remove existing panel and store at the Districts' designated location. Re-installation will be contracted separately.

3 Change: the polyisocyanurate insulation for the low slope roofs must be coated glass facer product meeting ASTM C 1289-06, Type II, Class 2, Grade 2 (20 psi).

4 Clarification: the asphalt shingle basis of design is GAF HD, Landmark AR and Tamko Heritage.

DESIGN TEAM LEAD:

NAME: Joe Mileti-Central States Roof Consulting

ADDRESS: 16209 Pepper View CT

Chesterfield, MO 63005

TELEPHONE: 314-560-3038

FAX: 636-216-0096

E-MAIL: miletij@sbcglobal.net

SIGNATURE: J. Mileti